ENGINEERING DEPARTMENT

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification dated 29th May 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M., on 15th June 1936, for constructing drains in Chintamani Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by 15th August 1936.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for constructing drains in Chintamani Town" in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer in Mysore who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Director of Health will be final and legally binding.

Abstract estimate of quantities of work for constructing drains in Chintamani Town.

No.	Description of work	Unit	Quantity
1	Constructing silk pattern drains, burnt stone slabs, cheeks at sides and surki concrete bed by forming channel at the centre of the concrete bed and surface plastered over with ½" cement mortar, joints of slabs cement pointed, including earthwork excavation of the drains, etc., complete as per designs—		
	1. Design of 4" (2) Section	R.ft.	600
	2. Do 5" do	,,	640
	3. Do 7" do	,,	460
	4. Do 3" Section	,,	820

Notification dated 29th May 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M., on 15th June 1936, for constructing drains in Banawar Town, Arsikere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the 15th August 1936.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash (no cheques will be accepted) as earnest money, and be superscribed " Tender for constructing drains in Banawar Town, Arsikere Taluk," in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer in Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Director of Health will be final and legally binding.

Abstract estimate of quantities of work for constructing drains in Banawar Town, Arsikere Taluk.

No.	Description of work	Unit	Quantity
I	Constructing silk pattern drain with burnt stone slab cheeks at sides and surki concrete bed by forming channel at the centre of the concrete bed and surface plastered over with ½" cement mortar joints of slabs cement pointed, including earth work excavation of the drain, etc., complete as per type designs—		
	1. Design of 2" Section	R.ft.	1,605
	2. Do 3" Section	,,	200
	3. Do 4" (2) Section	,,	500
	4. Do 5" (1) Section	,,	500
II	Removing the slab stones of the existing drains	Sq.ft.	1,600

B. R. GARUDACHAR,
Sanitary Engineer.

TUMKUR DIVISION.

Abstract Notification dated 22nd May 1936.

Attention of the public is drawn to notification calling for tenders for widening the bund of Kodagihalli tank on Nademavinpur-Amruthur Road, published in pages 608-609, Part VI of the *Mysore Gazette*, dated 30th April 1936.

The date fixed to receive tenders is extended to 13th June 1936 from 18th May 1936.

Earnest money in cash of Rs. 200 should accompany the tender.

N. G. KRISHNA IYENGAR,
Executive Engineer.